

9-23-86

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Menominee
(County)

Located in:

Corner Code #

BY LAW DIRECTED BY
THE CLERK

1. Public Land Survey

T ___ R ___

T ___ R ___

T ___ R ___

T ___ R ___

2. Property Controlling
in Section

S 1 T 35N R 29W

S ___ T ___ R ___

3. Miscellaneous
Property in Sec.

S ___ T ___ R ___

S ___ T ___ R ___

13, 16.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David Babbitt, in a field survey on 8/25, 1986, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

13. Southeast 1/16 corner of Section 1. No previous record of a survey marker at this location.

16. East 1/16 corner on the south section line of Section 1. No previous record of a survey marker at this location.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

13. Set at the intersection of a line beginning at the south 1/16 corner on the east section line and running westerly parallel to the south section line with a line beginning at the east 1/16 corner on the south section line and running northerly parallel to the east section line of Section 1. Found iron N85E, 133.7' from this point but it is not recorded in land corner records and does not fit a proper 1/16 corner location for a sub'n. of Section 1.

16. Set MPOL between the south 1/4 corner and the SE section corner of Section 1. There is a 1/2" rod and a short steel post N74E, 18.9' from this point, but it is not recorded in land corner records and does not fit a proper 1/16 corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

13. 1" pipe with 4" alum. cap.
9" oak N61W, 15.78'
10" oak N45E, 17.02'
6" oak S77E, 23.92'
8" oak S22W, 23.10'
Found iron rod N85E, 133.7'

16. 9" r.pine S33W, 46.6' 1" pipe with
4" w.pine S10E, 25.8' 4" alum. cap.
4" oak N40W, 7.7'
3" w.pine N40E, 41.9'
Found 1/2" rod N74E, 18.9'

Signed by David B. Babbitt

Date 9-23-86

Surveyor's Michigan License No. RLS 21558