

01/16

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Menominee (County) Located In: Corner Code #
1. Public Land Survey T 35N R 29W M-1MC, M-2
2. Property Controlling in Section S 1 T 35N R 29W 14
3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

I, David Babbitt, in a field survey on 9/22/86, 19, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13. Numbers 1-36 are placed in the grid cells.

- A. Description of original monument and accessories and/or subsequent restoration:
M-1MC. Meander corner on the East section line of Section 1. Lynn 10" in diameter for meander post. Hemlock 14", S12E, 17 Lks. Sugar 14", S50W, 43 Lks.
M-2. East 1/4 corner of Section 1. Wood post. Beech 8, N13 1/2 W, 32 Lks. Beech 14, S4W, 46 Lks.

14. S 1/16 corner on the East section line of Section 1. Nothing previously on record.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
M-1MC. Could not identify OBT's. Riverbank is very stable, large trees on steep bank at water's edge. Original meander record fits existing shoreline well. Set monument for meander corner by fitting meander record to existing shoreline.
M-2. Set by single proportion to the GLO record between the Menominee River MC north and the SE section corner of Section 1 to the south.
14. Set MPOL between the East 1/4 corner and the SE section corner of Section 1. Found 1/2" iron rod, S87E, 111.1' but could find no record of its origin.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-1MC. DNR Monument. 8" S.Maple, N74E, 12.1'
4" Hickory S57E, 31.95'
4" S.Maple, S6W, 26.0'
4" Ash, S71W, 48.9'
M-2. DNR Monument. 6" White Pine, 53.7', N70W.
8" White Pine, 59.6', N6W.
8" Oak, 57.05', S58E.
8" Oak, 19.55', S83W.
14. DNR Monument. 12" White Pine, 33.3', N50E.
3" R.Maple, 22.4', S8E.
7" R.Maple, 17.15', S52W.
7" Cherry, 23.3', N65W.

Signed by David B. Babbitt Date 1-27-87
Surveyor's Michigan License No. RLS 21558