

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

Chairman  
 PAGE # 497 BK 5  
 BARBARA MORRISON  
 REGISTER OF DEEDS  
 MENOMINEE MI 49838  
 97 JUL 23 PM 3:34  
 RECEIVED FOR RECORD

For corners in  
MENOMINEE  
 (County)

Located In: Corner Code #

1. Public Land Survey T5N R 29W K-9  
 T      R       
 T      R       
 T      R     

2. Property Controlling in Section S      T      R       
 S      T      R     

3. Miscellaneous Property in Sec. S      T      R       
 S      T      R     

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, William Lenca, in a field survey on June 26, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1852: Original Survey by Francis Coleman - B.T.'s - W. Pine, 30" - N42°E - 22 lks.; W. Pine, 18" - S50°W - 40 lks. All original evidence for this corner has been destroyed by county road improvements.
- 1945: Record of Survey by M.S. McNabb, in his capacity as Deputy County Surveyor, states that he established an iron in accordance with existing improvements - in road South & East. Wit.'s: Cor. Fence Post - S32°E - 39.10'; Twin Pine, 9" - N70°W - 70' (see page 9, County Surveyors Record Book.)
- 1987: L.C.R.C. No. 785 by William Lenca, RLS No. 26461, states "Found Iron Bolt set by M.S. McNabb in 1945 Survey." Wit.'s: Co. Rd. Sign Post - S50°E - 54.62'; Power Pole - S45°W - 49.35'; 1/2" dia. Iron Pipe - S60°W - 8.03'; 5/8" x 24" Iron Rod/ID cap - North - 33.00'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We recovered a 1 inch square Iron Bolt in position matching closely with M.S. McNabb's record distances to Corners 1/2 mile North and 1/2 mile South. We also recovered the following Witnesses from L.C.R.C. No. 785: Co. Rd. Sign Post - S50°E - 54.62'; Power Pole - S45°W - 49.35'; 1/2" dia. Iron Pipe - S60°W - 8.03'; 5/8" x 24" Iron Rod/ID cap - North - 33.00' This corner has been used by local surveyors for over 50 years, and is accepted as the best available evidence of the position of the original corner. Note: We were unable to remove the Iron Bolt, and since there was a 3 inch square metal flange around it, we were unable to place a monument over the top of it. We therefore accepted the iron bolt as the corner monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Accepted existing 1 inch square Iron Bolt:

5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N10°W	32.85 feet	
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	S41°E	52.68 feet	2.6' W. of Co. Rd. Sign
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	S46°W	46.41 feet	3.5' N. of Power Pole
1/2" dia. Iron Pipe	S60°W	8.03 feet	
Metal Survey Sign Post	N10°W	34.0 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Jul. 09, 1997  
 Surveyor's Michigan License No. 26461



REMONUMENTATION

DEC 2 1997  
 COMMISSION

497