

SURVEY & REMONUMENTATION

FEB 11 1998

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. of 1990 On 12/13 1997
Mike Davis RLS
Chairman

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

MENOMINEE
(County)

Located in:

Corner Code #

1. Public Land Survey

T35N R. 25W M-2/3 (001)

T R #002 ✓

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

SAME AS CORNER A-2/3 (002) T35N-R24W

I, William Lenca, in a field survey on June 24, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1847: Original Survey by James H. Mullett - B.T.'s - Cedar, 12" - N37°W - 60 lks.; Cedar, 5" - N02°W - 50 lks. All original evidence for this corner has been destroyed by ice shoves.
- 1970: Plat of Survey by George B. Wilson, RLS No. 17607, shows this corner as it relates to other corners in Section 1, T35N-R25W, and describes it as "set concrete monument". The survey also shows that Wilson re-established the original Government Meanders in order to establish this Meander Corner.
- 1992: CERTIFIED SURVEY No. 775 by William Lenca, RLS NO. 26461, shows this corner as it relates to other corners in Section 1, T35N-R25W. The map legend indicates that the corner monument is a 4" dia. concrete monument.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

The concrete monument described in Wilson's 1970 Plat of Survey and in Certified Survey No. 775 had been destroyed by high water and ice shoves. Since this corner had been re-established by retracement of original government meanders by George B. Wilson. We had accepted this corner in 1992 as a careful and faithful reestablishment of the position of the original corner. Since the corner monument has now been destroyed, we re-established a reference monument on line between the destroyed Meander Corner and the E1/4 Corner of Section 1, T35N-R25W and 66 feet North of the old Meander Corner.

C. Description of monument for corner and accessories established to perpetuate localing the position of the corner:

Set 2" dia. Aluminum Pipe 30" long/3-1/4" dia. Alum cap stamped for corner location:

9" dia. Cedar	N23°E	18.37 feet	Scr. NBT
8" dia. Tamarack	S86°E	8.99 feet	Scr. NBT
8" dia. Tamarack	S66°W	48.37 feet	Scr. NBT
Metal Survey Sign Post	N73°W	1.15 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date July 18, 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 19
REVISED MAY 14, 19
REVISED JAN., 19
REVISED OCT., 19

568

REGISTERED LAND SURVEYOR
WILLIAM LENCA
No. 26461

97 DEC 22 AM 11:25

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

