

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 36 & 37 N.R. 24 & 25 W


Menominee & Delta COUNTY

DESCRIPTION OF CORNER Town corner for sections T37N R25W 36/31 T37N R21W
T36N R25W 1/6 T36N R21W

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 6/22/67, Frank J. Bray

WITNESSES TO CORNER..... 9^m Cedar (S31)(NBT) N 20° E, 02 Links



9^m Cedar (S6)(NBT) S 09° E, 32 Links

10^m Cedar (S36)(NBT) N 55° W, 11 1/2 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was - reestablished by double proportioned measurement between section corners 1 mile to north 1 mile to east and 1/4 corners to south and west. Stream to east checks fairly good. No original evidence found.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 8/22/67
REGISTERED LAND SURVEYOR