

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 37/36 N. R. 24 W


Menominee & Delta COUNTY

DESCRIPTION OF CORNER Section corner for sections 31/32 T37N R24W
6/5 T36N R24W

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 7/3/67, Frank J. Bray

WITNESSES TO CORNER..... 9" Cedar (S5)(NBT) S 48° E, 30½ Links



9" Tamarack (S31)(NBT) N 85° W, 28½ Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from old post and point of older post. Blazed trees and squared tree in area. Corner checkes good with other corners on town line. No original evidence found.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 8/22/67
REGISTERED LAND SURVEYOR