

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 36 N.R. 24 & 25


Menominee COUNTY

DESCRIPTION OF CORNER 1/4 corner for sections T36N R25W 1/6 T36N R25W

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 6/20/67, Frank J. Bray

WITNESSES TO CORNER..... 18" W. Pine (1/4S)(NBT) N 38° W, 22 1/2 Links



16" Cedar (1/4S)(NBT) S 30° W, 38 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed on line between town corner to north and Floyd's defaced corner 5.00chs to south. Original notes mention 1/4 corner was set 5.00chs north of Floyd's post. Blazed in vicinity of corner.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 8/23/67
REGISTERED LAND SURVEYOR