

✓
MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 36 N.R. 24 W


Menominee COUNTY

DESCRIPTION OF CORNER Section corner for sections $\frac{6}{5}$ $\frac{7}{8}$

CORNER MONUMENT 1" Iron pipe with 4" Aluminum cap

DATE MONUMENT PLACED AND WITNESSED 10/20/67, Frank J. Bray

WITNESSES TO CORNER..... 11" Cedar (S.5)(NBT) N 61° E, 48 Links



7" Cedar (S.6)(NBT) N 50° W, 11 Links

12" Cedar (S.7)(NBT) S 25° W, 25 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced from down rotted ~~metal~~^{wood} post and down cedar rotted but axe marks and possible ~~portion~~ portion of scribe mark visible on overgrowth. Cedar face had been chopped out in the past.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 11/8/67
REGISTERED LAND SURVEYOR