

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 36 N.R.'s 24 & 25W


Menominee COUNTY

DESCRIPTION OF CORNER Section corner for sections T36N, R25W ^{24/19} 25/30 T36N, R24W

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 5/15/68, F. J. Bray

WITNESSES TO CORNER..... 7" W. Pine (S.24 NBT) N 70° W, 41 links



12" W. Pine (S.30 NBT) S 44° E, 31½ links

16" R. Pine (S.25 NBT) S 56° W, 49 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from rotted and chopped white pine stump which has notch but no iron marks. And old down and rotted fence corner.
(W. Pine stump 18" S 64° W 13 links)

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 7/10/68
REGISTERED LAND SURVEYOR
Frank J. Bray