

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 36 N. R. 24W


Menominee COUNTY

DESCRIPTION OF CORNER Section corner for sections ^{7/8} 18/17

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 7/22/68, F. J. Bray

WITNESSES TO CORNER..... 14" Cedar (S.8) (NBT) N 16° E, 21 links



8" Cedar (S.7) (NBT) S 67° E, 24 links

10" Cedar (S.18) (NBT) S 46° W, 09 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was reestablished by double proportioned measurement between 1/4 corners, 1/2 mile to east, to south and to west and section corner one mile to north. No original evidence found.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 8/16/68
REGISTERED LAND SURVEYOR
Frank J. Bray