

REMONUMENTATION

FEB 11 1998

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 10/31, 199 97
Mr. Davis RLS
Chairman

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MENOMINEE

(County)

Located In:

Corner Code #

1. Public Land Survey

T36N R. 24W

E-04

T ___ R ___

T ___ R ___

T ___ R ___

2. Property Controlling
in Section

S ___ T ___ R ___

S ___ T ___ R ___

3. Miscellaneous
Property in Sec.

S ___ T ___ R ___

S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on Aug. 25, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

REGISTERED RECORD
97 NOV 21 PM 3:17
PAGE 576, BK 5
BARBARA JOHNSON
REGISTERED RECORD

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8	20	9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
1848: Original Survey by James H. Mullett - B.T.'s - Hemlock, 10" - S79°W - 14 lks.; Hemlock, 8" - N70°E - 19 lks. All original evidence for this corner has been destroyed by state highway improvements.
1968: L.C.R.C. No. 562 (Vol. 3) recorded by Frank Bray: Found 1" Iron Rod in Monument Box set by MDOT in 1948 - they found 2" iron pipe - new Witnesses: 11" soft maple - S89°W, 70.5 lks; Power Pole - N20°W - 174.5 lks; West edge of pavement - East - 03 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
We recovered a 1" diameter Iron Rod in a Monument Box 4" below the shoulder and 2' +/- West of the pavement of Highway M-35 per LCRC No. 562. This corner has been accepted and used by local surveyors for almost 50 years, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set 5/8" x 24" Iron Rod/3-1/4" Alum. cap stamped for corner location in Monument Box:

N.W. Corner of Garage	N62°E	141.82 feet	
30" dia. Maple	S75°W	112.70 feet	Scr. NBT
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N16°W	114.81 feet	
Metal Survey Sign Post	N86°W	29.07 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with EDM. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Aug. 28, 1997
Surveyor's Michigan License No. 26461

516