

SURVEY & REMONUMENTATION

FEB 11 1998

Peer Group Under Act 345 of
P.A. of 1990 On 10/31, 1997
Michael RUS
Chairman

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MENOMINEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T6N R 24W</u>	<u>E05</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

REGISTERED FOR RECORD
97 NOV 21 PM 3:17
PAGE 3 514 285
MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS
REGISTERED FOR RECORD
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William Lenca, in a field survey on Aug. 25, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

- A. Description of original monument and accessories and/or subsequent restoration:
1848: Original Survey by James H. Mullett - B.T.'s - Birch, 12" - S22°E - 16 lks.; Cedar, 6" - S37°W - 11 lks. All original evidence for this corner has been destroyed by county road improvements.
1968: L.C.R.C. No. 566 (Vol. 3) recorded by Frank Bray: Sct 1-1/2" Iron Pipe 18 lks north of centerline of E-W gravel road
Witnesses: 12" Cedar - N29°W - 67 lks; 12" Cedar - N07°E - 38.5 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We identified the corner by a tipped 1-1/2 inch diameter iron pipe and 2 existing Cedar B.T.'s as described in L.C.R.C. No. 566. We restored the corner position by straightening the existing iron pipe until it fit the 2 existing B.T.'s. This corner has been accepted and used by local surveyors for over 30 years, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Sct 2" dia. Aluminum Pipe 30" long/3-1/4" dia. Alum cap stamped for corner location:

12" dia. Cedar (Ex. B.T.)	N07°E	25.86 feet	Scr. NBT (1/4 S)
14" dia. White Spruce	S25°E	33.33 feet	Scr. NBT
9" dia. Cedar	S41°W	35.27 feet	Scr. NBT
9" dia. Cedar	N50°W	22.11 feet	Scr. NBT
Metal Survey Sign Post	North	8.7 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Aug. 28, 1997

514