

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

McDANIEL RLS  
Chairman

For corners in  
MENOMINEE  
(County)

Located In:	Corner Code #
T36N R 24W	G02
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

- Public Land Survey
- Property Controlling in Section
- Miscellaneous Property in Sec.

RECEIVED FOR RECORD  
96 OCT - 7 PM 3:26  
PAGE # 356 BK 4  
BARBARA MORRISON  
REGISTER OF DEEDS  
MENOMINEE COUNTY

Register of Deeds Stamp & File Number

- Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- Private Claims \_\_\_\_\_

I, William Lenca, in a field survey on Apr. 23, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5			4	●	3		2		1
3												
4	7		8			9		10		11		12
5												
6	18		17			16		15		14		13
7												
8	19		20			21		22		23		24
9												
10	30		29			28		27		26		25
11												
12	31		32			33		34		35		36
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett - B.T.'s - Cedar, 8" - N27°W - 48 lks; Cedar, 5" - S30°E - 150 lks. No original evidence for this corner was recovered.
- 1979: Certified Survey No. 153 by George B. Wilson, RLS No. 17607, describes this corner as a "pin" and shows its position in relation to other corners in Section 4, T36N-R24W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a 5/8" diameter iron rod in line with road centerlines South and West. The existing iron rod matches the position shown in Certified Survey No. 153. This corner has been accepted and used by local surveyors for at least 17 years, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Set 2" dia. Aluminum Pipe/3-1/4" dia. Alum. cap stamped for corner location:

8" dia. Cedar	N37°E	29.43 feet	Scr. NBT
10" dia. Cedar	S71°E	30.33 feet	Scr. NBT
10" dia. Cedar	S51°W	47.68 feet	Scr. NBT
12" dia. White Spruce	N38°W	38.45 feet	Scr. NBT
Metal Survey Sign Post	North	14.95 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date Apr. 27, 1996