

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 36. NR 25 W. . . .

Menominee

----- COUNTY

DESCRIPTION OF CORNER Section Corner common to 27, 28, 33, 34. -----

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" Brass Cap. -----

WITNESSES TO CORNER 10" Cedar N 30°E 92 Links. -----

12" Hemlock N 62°W 32 Links. -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

Corner set by Double Proportionate Measurement. N.-E.-W. to good corners and
South to a Swamp edge & No evidence of Original Corner.

The mile South is long-- 87.70 chs. This is due to an error in the Original Survey.

Corner placed and witnessed August 22, 1955.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 12/9/55.
REGISTERED LAND SURVEYOR