

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 36 NR 25 W

Menominee

COUNTY

DESCRIPTION OF CORNER Section Corner common to 16, 17, 20, 21

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" Brass cap.

WITNESSES TO CORNER 8" Balsam N 52°W 37 Links.

6" Soft Maple N 77°E 21 Links.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

Corner set by proportionate measure, North to a Stream and a Bank, East to a small Stream. There is no evidence of Original Sec. Cor.

The half mile West is short. Chainage--37.49 chs. This is an error in the Original Survey carried West from the mile between Secs' 14-23.

Corner placed and witnessed August 22, 1955.

SURVEYORS SEAL

SIGNED *Billy D. Buckles* DATE 12/9/55.
REGISTERED LAND SURVEYOR