

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 36 NR 25 W. . . .

Menominee

----- COUNTY

DESCRIPTION OF CORNER Section Corner common to 19, 20, 29, 30. -----

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" Brass cap. -----

WITNESSES TO CORNER 8" Aspen N 25° E 41 Links. -----

9" Aspen S 27° E 67 Links. -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR  
RESTORED.

Corner set by Double Proportionate Measure. North to a good Section Corner,  
South, East, West to Swamp edges.  
There are a few traces of Hemlock stumps in this area but no evidence of Corner.

Corner placed and witnessed June 21, 1955.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 12/9/55.  
REGISTERED LAND SURVEYOR