

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 37/36 N.R. 25 W


Menominee COUNTY

DESCRIPTION OF CORNER 1/4 corner for sections ³⁵ T37N R25W
2 T36N R25W

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 7/11/67, Frank J. Bray

WITNESSES TO CORNER..... 6" R. Pine (1/4S)(NBT) N 74° W, 44 Links



11" R. Pine (1/4S)(NBT) S 47° E, 94 1/2 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed single proportioned distance between section corners to east and west and in line with old E-W blazed a burnt pine stub which has upper face and faint scribe marks which possibly was an extra BT not mentioned in original notes face set corner.
(W.Pine 10" West 65 Links)

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 8/22/67
REGISTERED LAND SURVEYOR