

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION



LAND CORNER RECORD

T. 36 N.R. 25


Menominee COUNTY

DESCRIPTION OF CORNER 1/4 corner for sections 2/1

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 7/10/67, Frank J. Bray

WITNESSES TO CORNER..... 12" Cedar (1/4S)(NBT) S 01° W, 42 Links



7" Cedar (1/4S)(NBT) N 65° E, 14 1/2 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed on line and the single proportioned measurement between section corners to north and to south. No original evidence found.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 8/22/67
REGISTERED LAND SURVEYOR