

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 36 N.R. 25


Menominee COUNTY

DESCRIPTION OF CORNER Section corner for sections ^{15/14} 22/23

CORNER MONUMENT 1" Iron pipe with 4" Aluminum cap

DATE MONUMENT PLACED AND WITNESSED 10/26/67, Frank J. Bray

WITNESSES TO CORNER..... 6" B. Ash (S15)(NBT) N 51° W, 43 Links



14" Tamarack (S14)(NBT) N 15° E, 119 Links

8" W. Birch (S14)(NBT) N 88° E, 44 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Placed at old wood post with point of older rotted post along it side. Cedar roots in proper bearing and distance from post may have been original BT corner checks fairly well with corners in area.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 11/8/67
REGISTERED LAND SURVEYOR