

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 36 N.R. 25


Menominee COUNTY

DESCRIPTION OF CORNER Section corner for sections $\frac{4}{3}$ $\frac{9}{10}$

CORNER MONUMENT 1" Iron pipe with 4" Aluminum cap buried in old township road.

DATE MONUMENT PLACED AND WITNESSED 10/10/⁶⁷~~66~~, Frank J. Bray

WITNESSES TO CORNER..... 11" Cedar (S3)(NBT) N 15° W, 33 Links



7" Cedar (S9)(NBT) S 49° W, 47 Links

Location post, south, 25 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Placed in approximate $\frac{1}{2}$ of old E-W township rd, which was intended to be on section line and the proportioned distance to $\frac{1}{4}$ corners to east and to west, corner checks well with river to west. No original evidence ~~found~~ found.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 11/8/67
REGISTERED LAND SURVEYOR