

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 37/36 N.R. 25 W


Menominee COUNTY

DESCRIPTION OF CORNER Section corner for sections $\frac{35}{36}$ T37N R25W
2/1 T36N R25W

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 7/10/67, Frank J. Bray

WITNESSES TO CORNER..... 10" Hemlock (S36)(NBT) N 77° E, 58½ Links



7" Hemlock (S1)(NBT) S 36° E, 46 Links

10" W. Pine (S2)(NBT) S 61° W, 15½ Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from wood post. Residents of area say this corner was set by Menominee Co. Surveyor in the early 1930's. Post checks well with land calls in original field notes to north, east and west and with section corners to north and south. However there is a shortage to 1/4 corner to east and surplus to section corner to west. If corner was set on line and single proportioned distance with corners to east and to west it would not check well with land features nor to corners both north and south. No original evidence found.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 8/22/67
REGISTERED LAND SURVEYOR