

✓
MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 36 N.R. 25 W


Menominee COUNTY

DESCRIPTION OF CORNER 1/4 corner for sections $\frac{2}{11}$

CORNER MONUMENT 1" Iron pipe with 4" Aluminum cap

DATE MONUMENT PLACED AND WITNESSED 10/2/67, Frank J. Bray

WITNESSES TO CORNER..... 4" S. Maple (inclump)(1/4S)(NBT) N 85° W, 13 Links



8" Aspen (1/4S)(NBT) S 61° E, 37 1/2 Links

W. Pine stump S 11° E, 17 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced from W. Pine stump which has blazes and notches and axe marks / and from rotted Hemlock stump bottom which check with distances and bearings in field notes. Swamp ~~check with hand distances~~ edges to E and W check.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 11/2/67
Frank J. Bray
REGISTERED LAND SURVEYOR