

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 36 N.R. 25 W


Menominee COUNTY

DESCRIPTION OF CORNER Section corner for sections <sup>9/10</sup>16/15

CORNER MONUMENT 1/2"x12" reinforcing rod buried in road 6"

DATE MONUMENT PLACED AND WITNESSED 9/29/67, Frank J. Bray

WITNESSES TO CORNER..... 9" Cedar (S16)(NBT) S 21° W, 52 Links



25" W. Pine (S15 NBT) S 55° E, 126 Links

Location post, north, 40 Links

AND

9" Cedar (S9)(NBT) N 12° W, 108 Links

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Placed in the approximate center of county road and the proportioned distance between section corners to east and to west. Checks well with river crossing to west.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 11/8/67  
REGISTERED LAND SURVEYOR