

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 37/36 N.R. 25 W


Menominee COUNTY

DESCRIPTION OF CORNER Section corner for sections $\frac{33}{4}$ T37N R25W
 $\frac{4}{3}$ T36N R25W

CORNER MONUMENT 1" Iron pipe with 4" Aluminum cap

DATE MONUMENT PLACED AND WITNESSED 9/6/67, Frank J. Bray

WITNESSES TO CORNER..... 7" H. Maple (S3)(NBT) S 37° E, 70 Links



7" H. Maple (S4)(NBT) S 25° W, 14½ Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Placed on line and single proportioned measurement between 1/4 corners 1/2 mile to east and to west. Corner checks well with it's position on ridge. Squared basswood near. No original evidence found.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 11/8/67
Frank J. Bray
REGISTERED LAND SURVEYOR