

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>36</u> N. S., R. <u>25</u> E. W.	<u>I-6</u>
2. PROPERTY CONTROLLING IN SECTION_____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on June 4 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

West  $\frac{1}{4}$  corner - Section 14; Wood Post, Cedar 10 - S55 $\frac{1}{2}$ °W - 28 lks.; Tam. 8 - S86°E - 09 lks. Searched thoroughly on three separate occasions but found no sign of the O.B.T.'s.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

Set at mid point by measuring between the N.W. and S.W. section corners of Sec. 14 but at a point 124.2' west of a straight line between said section corners. This was done because the swamp calls from the notes of the original survey at both 37.00 chs. and 53.00 chs. did not fit at all using a straight line from section corner to section corner. There is, however, a line of old blazes in the south  $\frac{1}{2}$  mile leading from the S.W. section corner to this point and using this point as the  $\frac{1}{4}$  corner both of the above mentioned swamp calls fit well. Therefore, I believe that this is nearer the original  $\frac{1}{4}$  corner location than a straight line would be.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

1" pipe, 4" aluminum cap; 9" Tamarack - N45°W - 52.7'; 16" Cedar - N15°E - 27.3'; 7" W. Birch - S71°E - 20.6'; 4" W. Spruce - S7°W - 15.4'.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 6-26-80  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558