

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Menominee</u> <small>(County)</small>	Located In:	Corner Code <del>##</del>
1. Public Land Survey	T <u>36N</u> R <u>25W</u>	<u>F-11.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David Babbitt, in a field survey on 6/30/86, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

F-11. South 1/4 corner of Section 28. 1" pipe with 4" brass cap. Mich. Cons. Dept. 1955.  
 12" aspen, S70E, 11 Lks.  
 9" w.birch, S75E, 21 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-11. Found 1" pipe with 4" brass cap (broken) lying beside logging road. Set new monument from 1955 NBT (9" w.birch, S75E, 21 Lks.)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-11. D.N.R. Monument.  
 5" r.maple S22E, 26.3'  
 9" balsam fir, S60W, 3.6'  
 10" r.maple N18W, 14.45'  
 5" r.maple N58E, 24.65'

Signed by David B. Babbitt Date 9-11-86  
 Surveyor's Michigan License No. 21558