

OK.  
B.712

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Menominee</u> <small>(County)</small>	Located In:	Corner Code <i>##</i>
1. Public Land Survey	T <u>36N</u> R <u>25W</u>	<u>H-3, I-3.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David Babbitt, in a field survey on 10/21/87, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

H-3. North 1/4 corner of Section 10. Michigan Dept. of Conservation, 11-8-67.  
1" pipe w/4" aluminum cap. 6" aspen, N69W, 6 Lks.  
8" aspen, S63E, 34 Lks.

I-3. NE section corner of Section 10. Mich. Department of Conservation, 10/3/67.  
1" pipe w/4" aluminum cap.  
8" spruce, S01E, 75½ Lks.  
16" balsam, N05W, 107½ Lks.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

H-3. Found 1" pipe with 4" aluminum cap. The northwest NBT is in place alive with both faces grown over. The southeast NBT was cut some time ago and the stump is nearly rotted away. Rewitnessed monument as found.

I-3. Found 1" pipe with 4" aluminum cap. Both NBT's are in place but the 16" balsam is dead and the top broken off. Re-witnessed monument as found.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

H-3. 1" pipe w/4" aluminum cap.	I-3. 1" pipe w/4" aluminum cap.
5" w.pine, N84W, 46.0'	6" spruce, N79E, 35.8'
6" w.pine, N15E, 6.1'	7" spruce, S25E, 43.9'
5" w.pine, S63E, 31.2'	9" spruce, S47W, 72.0'
6" w.pine, S46W, 48.7'	5" balsam, N5E, 31.9'

Signed by David B. Babbitt Date 12-3-87  
Surveyor's Michigan License No. 21558