

OK
B11109

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Menominee
(County)

Located In:

Corner Code ~~##~~

- 1. Public Land Survey T 36N R 25W G-9.
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David B. Babbitt, in a field survey on 10/19/87, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-9. SW section corner of Section 22. Michigan Dept. of Conservation. 7-24-1952.
1" pipe with 4" brass cap - one OBT in place. 24" w. pine, S28W, 81 Lks.
8" cedar, S76E, 64 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-9. Found 1" pipe with brass cap marked Mich. Dept. of Conservation, Forestry Division stuck loosely in ground about 20' east of where it should have been. Found stump of 24" w.pine NBT cut just above the notch. Found cedar NBT alive but with both faces entirely grown over. Opened bottom blaze to verify it and found it mostly eaten away by ants. Notch and part of "B" and "T" shown in reverse on overgrowth. Reset mon. from 1952 NBTs.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-9. 1" pipe w/4" brass cap.
10" w.spruce, S83E, 39.6'
12" w.ash, N37W, 31.9'
6" w.pine, S58W, 30.5'
7" w.pine, S26W, 24.15'

Signed by David B. Babbitt Date 12-3-87
Surveyor's Michigan License No. 21558