

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Menominee
(County)

Located In:

Corner Code \neq

- | | | | | | | |
|------------------------------------|---|------------|---|------------|-------------|-------|
| 1. Public Land Survey | T | <u>36N</u> | R | <u>25W</u> | <u>J-3.</u> | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| 2. Property Controlling in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 16 | | 17 | | 18 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, David B. Babbitt, in a field survey on 11/10, 19 87, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- J-3. South $\frac{1}{2}$ corner of Section 2. Michigan Department of Conservation, November 2, 1967.
 1" pipe with 4" aluminum cap. 4" S.Maple (in clump) N85W, 13 Lks.
 8" Aspen, S61E, 37 $\frac{1}{2}$ Lks.
 W.Pine stump, S11E, 17 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- J-3. Found 1" pipe with 4" aluminum cap. W.pine stump S11E, 17 Lks. with definite axe marks fits position of original bearing tree "w.pine 14, S11E, 17 Lks." both Conservation Department NBT's in place but the 8" aspen dead and blown down. Rewitnessed monument as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- J-3. DNR Monument.
 6" maple, S36E, 33.3'
 4" maple, S45W, 24.6'
 5" maple, N69E, 50.4'
 5" maple, N34W, 20.5'

Signed by David B. Babbitt

Date 2-9-88

Surveyor's Michigan License No. 21558