

RECEIVED

JUN 22 1992

RECREATION DIVISION
DEPT. OF NATURAL RESOURCES

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Menominee</u> <small>(County)</small>	Located In:	Corner Code <u>C-8</u>
1. Public Land Survey	T <u>36N</u> R <u>25W</u>	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Paul R. Bressette, in a field survey on December 17, 1990, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-8. West Quarter corner of Section 20. Restored in 1955 by Billy Buckler, RLS. Set 1" iron pipe with 4" brass cap witnessed by: 12" Sugar Maple N 53° E 36 links and an 12" Ironwood N 27° W 55 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-8. Found NBT's as described and 1" iron pipe with broken cap. Replaced existing pipe with 1" iron pipe with 4" aluminum cap with RLS number 19008.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-8. 1" iron pipe with 4" aluminum cap
 *15" Sugar Maple N 60° E 23.55'
 5" Sugar Maple S 41° E 24.75'
 5" Sugar Maple S 34° W 22.6'
 *12" Ironwood N 28° W 36.05'

* existing NBT's



Signed by Paul R. Bressette Date 6-17-92
 Surveyor's Michigan License No. 37270