

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Menominee  
(County)

Located In: \_\_\_\_\_  
Corner Code # \_\_\_\_\_

- 1. Public Land Survey  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling  
In Section S 35 T 36N R 25W \_\_\_\_\_  
S 35 T 36N R 25W \_\_\_\_\_  
9  
16
- 3. Miscellaneous  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6													
7													
8	18		17		16		15		14		13		
9													
10	19		20		21		22		23		24		
11													
12	30		29		28		27		26		25		
13													
	31		32		33		34		35		36		

I, Paul R. Bressette, in a field survey on 16 May 08, 1995,  
9 May 03, 1995, 19 \_\_\_\_\_,  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (9) East One-sixteenth corner of Section 35. Not set in original survey, no evidence of subsequent establishment.
- (16) East One-sixteenth corner common to Sections 35 and 2. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (9) Corner position established mid-point and on-line between the East and Center Quarter corners of Section 35.
- (16) Corner position established mid-point and on-line between the Southeast and South Quarter corners of Section 35.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |                        |                        |
|------------------------|------------------------|
| (9) DNR monument       | (16) DNR monument      |
| 9" Cedar N05E 65.8'    | 8" Cedar N62E 42.4'    |
| 8" Cedar S62E 67.35'   | 12" Cedar S70E 39.5'   |
| 6" Cedar S29W 27.4'    | 12" Hemlock S38W 27.2' |
| 7" Hemlock N77W 62.75' | 9" Cedar N32W 38.25'   |



Signed by Paul R. Bressette Date 11-15-95  
Surveyor's Michigan License No. 37270