

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Menominee
(County)

Table with columns: Located In, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. Contains numerical data for sections 6, 7, 18, 19, 30, 31, 32, 33, 34, 35, 36.

I, Paul R. Bressette, in a field survey on 7 May 03, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (6) Northeast One-sixteenth corner of Section 35. Not set in original survey, no evidence of subsequent establishment.
(7) North One-sixteenth corner common to Sections 35 and 36. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (6) Corner position established at the intersection of the North and East One-sixteenth lines of Section 35.
(7) Corner position established mid-point and on-line between the Northeast and East Quarter corners of Section 35.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- (6) DNR monument: 9" Maple N56E 61.4', 16" Maple S56E 26.45', 4" Maple S46W 57.05', 6" Maple N64W 23.75'
(7) DNR monument: 8" W. Birch N51E 11.05', 8" Aspen S54E 20.05', 15" Spruce S81W 20.35', 6" Spruce N48W 37.8'



Signed by Paul R. Bressette Date 11-15-95
Surveyor's Michigan License No. 37270