

Mr. James PLS
Chairman

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MENOMINEE
(County)

Located In: Corner Code #

- | | | |
|------------------------------------|-----------------------------|--------------|
| 1. Public Land Survey | T <u>36N</u> R <u>26W</u> | <u>M-2</u> |
| | T <u>36</u> R <u>R25</u> | <u>A-2</u> ✓ |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> | <u> </u> |

RECORDED FOR RECORD
56 DEC 20 11 0 34
PAGE # 389, BK 4
BUREAU OF LAND SURVEY
MICHIGAN DEPARTMENT OF NATURAL RESOURCES

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

SAME AS CORNER A-2 T36N-R25W ✓

I, William Lenca, in a field survey on Sept. 11, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1848: Original Survey by John Mullett - B.T.'s - Cedar, 6" - S29°W - 04 lks; Cedar, 6" - S70°W - 09 lks. All original evidence for this corner has been destroyed by fire and logging activities.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We located the single proportional position for this corner between the NE Corner of Section 1 and the SE Corner of Section 12, T36N-R26W, and searched this area for original evidence. Finding no such evidence, we set the corner at the above mentioned proportional location and accepted this location as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Set 2" dia. Aluminum Pipe/3-1/4" dia. Alum cap stamped for corner location:

7" dia. Cedar	N74°E	15.92 feet	Scr. NBT
9" dia. Cedar	S14°E	14.47 feet	Scr. NBT
9" dia. Cedar	S53°W	9.96 feet	Scr. NBT
8" dia. Cedar	N32°W	6.48 feet	Scr. NBT
Metal Survey Sign Post	South	1.1 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Oct. 07, 1996