

Approved by Menominee County  
 Land Survey Remonumentation  
 Peer Group Under Act 345 Of  
 P.A. Of 1990 On 12/12, 1996  
*McDermott*  
 Chairman

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MENOMINEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>36</u> N R <u>26</u> W	<u>M-3</u>
	T___ R___	<u>A-3</u> ✓
	T <u>36</u> R <u>25</u>	
	T___ R___	
2. Property Controlling in Section	S___ T___ R___	
	S___ T___ R___	
3. Miscellaneous Property in Sec.	S___ T___ R___	
	S___ T___ R___	

REGISTERED FOR RECORD  
 96 DEC 20 AM 9:34  
 DATA 388, BK 4  
 DANIELA WILSON  
 REGISTER OF DEEDS  
 REGISTER OF DEEDS STAMP & FILE NUMBER

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_  
 SAME AS CORNER A-3 T36N-R25W ✓

I, William Lenca, in a field survey on Sept. 11, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1848: Original Survey by John Mullett - B.T.'s - Sugar, 12" - S50°W - 11 lks; Fir, 10" - N22°W - 20 lks. All original evidence for this corner has been destroyed by fire and logging activities.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We located the single proportional position for this corner between the NE Corner of Section 1 and the SE Corner of Section 12, T36N-R26W, and searched this area for original evidence. Finding no such evidence, we set the corner at the above mentioned proportional location and found that it fit well with the GLO Notes stating that the corner fell on the South Margin of a Swamp. We accepted this location as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Set 2" dia. Aluminum Pipe/3-1/4" dia. Alum cap stamped for corner location:

12" dia. White Spruce	N32°E	20.38 feet	Scr. NBT
6" dia. White Ash	S41°E	26.48 feet	Scr. NBT
9" dia. Cedar	S48°W	43.46 feet	Scr. NBT
5" dia. Cedar	N70°W	16.39 feet	Scr. NBT
Metal Survey Sign Post	North	1.1 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
 Surveyor's Michigan License No. 26461

Date Oct. 07, 1996

388