

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County  
Land Survey Remonumentation  
Peer Group Under Act 345 Of  
P.A. Of 1990 On 12/27 1996  
Mel Davis Rcs  
Chairman

For corners in

MENOMINEE Located In: Corner Code #  
(County)

1. Public Land Survey T37N R 25W C13  
T R  
T36 R25 C-1 ✓  
T R  
2. Property Controlling S T R  
in Section S T R  
3. Miscellaneous S T R  
Property in Sec. S T R

REGISTERED FOR RECORD  
96 DEC 30 AM 9:08  
PAGE # 456 BK: 4  
BARBARA MORRISON  
REGISTER OF DEEDS  
MENOMINEE, MICHIGAN 49855  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

SAME AS CORNER C-1, T36N-R25W ✓

I, William Lenca, in a field survey on Sep 05, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1847: Original Survey by James H. Mullett - B.T.'s - Sugar Maple, 14" - N09°E - 09 lks.; Hemlock, 17" - N75°W - 20 lks. All original evidence for this corner has been destroyed by logging activities.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We determined the single proportional location of this corner between the S1/4 Corner (D-13) of Section 32 and the SW Corner (A-13) of Section 31, T37N-R25W. We searched this area and found no evidence of the original corner or of subsequent restoration. Our corner location fell 11.5' North and 10' East of an existing fence corner. Local residents stated that this fence was constructed in approximately 1960, and there was no corner evidence at the fence corner location. We therefore accepted the single proportional location as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2" dia. Aluminum Pipe/3-1/4" dia. Alum. cap stamped for corner location:

8" dia. Maple	N60°E	66.49 feet	Scr. NBT
10" dia. Maple	S26°E	40.90 feet	Scr. NBT
8" dia. Balsam	S72°W	16.99 feet	Scr. NBT
12" dia. Maple	N17°W	19.76 feet	Scr. NBT
Metal Survey Sign Post	N80°W	0.90 feet	



NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date Dec. 19, 1996

456