

11

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Menominee

(County)

Located In:

Corner Code //

- 1. Public Land Survey T 36N R 26M L6
2. Property Controlling in Section S 13 T 36N R 26M 8
3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

I, Paul R. Bressette, in a field survey on March 18, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13. Contains numbers 1-36 and corner markers.

A. Description of original monument and accessories and/or subsequent restoration:

- (L6) Center Quarter corner of Section 13. Not set in original survey, no evidence of subsequent establishment.
(8) West One-sixteenth corner of Section 13. Not set in original survey, no evidence of subsequent establishment. Old fence corner is about 40 feet west and about 100 feet south.
(9) East One-sixteenth corner of Section 13. Not set in original survey, no evidence of subsequent establishment.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (L6) Corner position established at the intersection of the North-South and East-West Quarter lines of Section 13.
(8) Corner position established mid-point and on-line between the West and Center Quarter corners of Section 13.
(9) Corner position established mid-point and on-line between the Center and East Quarter corners of Section 13.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- (L6) 1" pipe w/ 4" aluminum cap, 7" Cedar N73E 40.35', 8" Spruce S20E 63.85', 10" Spruce S66W 53.9', 7" Cherry N36W 47.7'. All trees are blazed, scribed (1/4S, BT) and painted. Measurements are to notch in butt blaze. Bearings are magnetic.
(8) 1" pipe w/ 4" aluminum cap, 12" Sugar N60E 38.4', 11" Sugar S30E 25.8', 12" Sugar S53W 56.65', 9" Sugar N43W 53.35'. All trees are blazed, scribed (1/16S, BT) and painted. Measurements are to notch in butt blaze. Bearings are magnetic.
(9) 1" iron pipe w/ 4" aluminum cap, 5" Spruce N19E 15.2', 4" Spruce S76E 29.7', 6" Elm S10W 4.55', 4" Spruce N72W 4.1'. All trees are blazed, scribed (1/16S, BT) and painted. Measurements are to notch in butt blaze. Bearings are magnetic.

Signed by Paul R. Bressette Date 8-14-96

Surveyor's Michigan License No. 37270