

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Menominee County (County) Located In: Corner Code #/
1. Public Land Survey T 36N R 26W I-8, J-7, J-8, K-8
2. Property Controlling S T R
In Section S T R
3. Miscellaneous S T R
Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

Register of Deeds Stamp & File Number

I, Paul Bressette, in a field survey on August 24, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13. Contains numbers 1-36 and symbols for corner locations.

A. Description of original monument and accessories and/or subsequent restoration:

I-8 Quarter Corner common to Sections 22 and 23. 1852: Francis Coleman, D.S. Set wood post witnessed by: Cedar 12 N49°E 22 links; Hemlock 10 S69°W 28 links.

J-7 Quarter Corner common to Sections 14 and 23. 1852: Francis Coleman, D.S. Set wood post witnessed by: Cedar 8 N45°E 16 links; Cedar 8 S36°W 15 links.

J-8 Center Quarter Corner of Section 23. Not set in original survey. No evidence of subsequent establishment.

K-8 Quarter Corner common to Sections 23 and 24. 1852: Francis Coleman, D.S. Set wood post witnessed by: Tamarack 9 N70°E 16 links; Tamarack 18 S42°W 34 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-8 Corner position re-established at intersection of ancient fences east, west and south. Cedar stump found in position for possible OBT.

J-7 Corner position re-established mid-point and on-line between the Northeast and Northwest corners of Section 23. Two cedar bottoms fit for original BT's but too rotted for positive identification.

J-8 Corner position established at the intersection of the North-South and East-West quarter lines of Section 23.

K-8 No evidence of original survey or restoration found. Ancient fences bearing north and west, and a single strand of wire bearing south and east were found. The intersection of the fences falls within 4 feet of a calculated mid-point and on-line position. Corner position re-established at the intersection of the ancient fences going north and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Table with 4 columns: I-8 DNR Monument, J-7 DNR Monument, J-8 DNR Monument, K-8 DNR Monument. Lists monument types, bearings, and distances.



Paul R. Bressette Date 9-28-93

37270