

Approved by Menominee County
 Land Survey Reestablishment
 Fee Group Under Act 346 of
 P.A. of 1995 On 10/26 1995
McC Davis RLS

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MENOMINEE
 (County)

Located In: Corner Code ##

1. Public Land Survey T 36N R 26W A-5
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

RECEIVED FOR RECORD
 95 NOV -8 AM 11:32
 PAGE # 247 BR4
 BANGS & JOHNSON
 REGISTERED LAND SURVEYORS
 MENOMINEE, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

William Lenca, in a field survey on Mar 23, 1995
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as
 expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
 on this certificate.

1. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by James H. Mullett (Twp Line) - B.T.'s - Tam, 6" - N38°W - 19 lks; Cedar, 12" - S38°W - 26 lks. All evidence for these B.T.'s was recently destroyed by construction of a gravel road.
- 1852: Original Survey (Section Subd.) by Francis Coleman - B.T.'s - Cedar, 10" - N50°E - 13 lks; Cedar, 12" - S36°E - 25 lks. Found remains of Cedar B.T. S36°E, 25 links. The other B.T. was recently destroyed by construction of a gravel road.
- 1984: L.C.R.C. No. 606 recorded by George B. Wilson, RLS No. 1760, states that a HDR Alum. Mon. was set from 4 original B.T.'s as described above. New Ties - Deep 1 magnets 1 foot North and 1 foot East.

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In a survey of Section 7 in March of 1995 we found a 3/4" x 5' long aluminum rod/3-1/4" dia. aluminum cap as established in L.C.R.C. No. 606. The corner falls in the SE corner of a gravel lane running South and East from this location. In the construction of the gravel road, all evidence of the original B.T.'s except one (S36°E, 25 links) was destroyed. We accepted the above described monument as a careful and faithful perpetuation of the position of the original corner.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Existing G. Wilson 3/4"x 60" Aluminum Pipe w/3 1/4" Alum. Cap Found 0.5' Below Surface of Gravel Drive:

6" dia. Cedar	N52°E	38.55 feet	Scr. NBT
8" dia. Cedar	S45°E	35.17 feet	Scr. NBT
8" dia. Cedar	N65°W	37.96 feet	Scr. NBT
9" dia. Cedar	N08°W	34.82 feet	Scr. NBT



NOTE: All bearings are magnetic bearings. All distances are measured with a steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date May 24, 1995
 Surveyor's Michigan License No. 26461

SURVEY & RE-MONUMENTATION