

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MENOMINEE  
 (County)

Located In:

Corner Code ==

1. Public Land Survey

T 35N R 27W  
 T 36 R 27  
 T 35 R 26  
 T 36 R 26

M-1  
M-13  
A-1  
(A-13) ✓

2. Property Controlling  
 in Section

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous  
 Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

(T36N-R27W - M-13) (T35N-R26W - A-1) (T36N-R26W - A-13) ✓

I, William Lenca, in a field survey on Aug. 31, 19 95,  
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
 expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
 on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1847: Original Survey by H. Floyd (Township Exterior) - B.T.'s - Hemlock, 14" - S25°E - 35 lks; Hemlock, 22" - N68°W - 32 lks. All original evidence has been destroyed by County Road improvements.
- 1985: L.C.R.C. No. 712 recorded by William Lenca, RLS No. 26461, states that a Deep-1 Magnet was set in place of an existing P.K. Nail in the centerline of county roads running East - West and North, and in line with an ancient fence running South. TIES: 10" Poplar - N56°W - 68.58'; Tel. Cable Box - S55°W - 47.63'; Stop Sign Post - N18°W - 50.40'; 4" Ced. - N23°E - 120.87'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

In an August, 1995 survey of Section 1, T35N-R27W, we found a Deep-1 Magnet in the centerline of County Road No. 358 (East - West), and in line with the centerline of a County Road running North and in line with an ancient fence running South from this location. We also found 2 bearing trees (10" Poplar - N56°W - 68.58 feet & 4" Cedar - N23°E - 120.87 feet), as recorded in L.C.R.C. No. 712, described in part "A". The measured distance from this corner to Corner M-2 (E1/4 Cor. of Sec. 1, T35N-R27W) is 2426.97 feet. This compares closely to the GLO distance of 2412.3 feet. This position has been used consistently for several years by local surveyors, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

- |   |       |            |
|---|-------|------------|
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | N26°E | 48.36 feet |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | S03°E | 34.97 feet |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | S55°W | 46.11 feet |
| 5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER" | N62°W | 61.01 feet |
| Metal Survey Sign Post  | S03°W | 35.3 feet  |

NOTE: All bearings are magnetic bearings. All distances are measured with a steel tape. All distances to trees are to nail in side of tree.

Signed by William Lenca Date Sept. 06, 1995  
 Surveyor's Michigan License No. 26461

RECEIVED FOR RECORDS  
 95 NOV - 8 AM 11:32  
 BARBARA JOHNSON  
 REGISTERED CLERK  
 REGISTERED LAND SURVEYOR

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



244