

1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 Of
P.A. Of 1990 On 12/28 19993
McC Davis
Chairman

For corners in

MENOMINEE
(County)

Located In:

Corner Code ##

- 1. Public Land Survey T 36N R 26W E-6
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

RECEIVED FOR RECORD
93 DEC 29 PM 3:55
PAGE # 39 Bl. 4
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

I, William Lenca, in a field survey on October 19, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL B.T.'s

- Hemlock, 12", N38°E, 3 lks
- Ironwood, 8", S45°W, 26 lks

Original Survey by Francis Coleman in 1852.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Set corner at intersection of old fences running North, South, East and West from this location. This position fits well with the Northwest Corner of Section 16, and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" by 4' aluminum rod/3 1/4" Alum. cap stamped for corner:

- 9" dia. Maple N41°E 9.89 feet
- 9" dia. Maple S16°E 16.59 feet
- 7" dia. Norway Pine S63°W 37.11 feet
- 9" dia. Maple N46°W 28.45 feet
- Sign Post N85°E 2.05 feet

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape; distances to trees are to nails in center of tree.

Signed by William Lenca

Date Oct. 28, 1993

Surveyor's Michigan License No. 26461

