

SURVEY & REMONUMENTATION

JAN 09 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Approved by Menominee County
Land Survey Remonumentation
Peer Group Under Act 345 of
P.A. Of 1990 On 7/13/2001
W.H. Davis RLS
Chairman

Book 6 Page 168

RECEIVED FOR RECORD
13 DEC 2000 10:16:09 A
BARBARA MORRISON
REGISTER OF DEEDS
MENOMINEE, MI 49858

Register of Deeds Stamp & File Number

For corners in <u>MENOMINEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 35N R 26W	H-1
	T ___ R ___	___
	T ___ R ___	___
	T ___ R ___	___
2. Property Controlling in Section	S ___ T ___ R ___	___
	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___
	S ___ T ___ R ___	___

4. Lot No. _____, Recorded Plat _____

5. Private Claims
SAME AS CORNER H-13, T36N-R26W

I, William Lenca, in a field survey on Jul, 1900 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
1848: Original Survey by James H. Mullett - B.T.'s - Hemlock, 12" - N85°E - 5 lks.; Hemlock, 12" - S73°W - 23 lks. All original evidence for this corner has been destroyed by County Road improvements.
1990: Certified Survey No. 697 recorded by William Lenca, RLS No. 26461, shows this corner as it relates to other corners in Section 3, T35N - R26W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found a railroad spike set in the centerline of county roads running East - West and North, and in line with an old fence running South matching the location shown in Certified Survey No. 697. This position fits well with measurements to corners 1/2 mile East and 1/2 mile West, and is accepted as the best available evidence of the position of the original corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 24" Iron Rod/3-1/4" dia. Alum. cap stamped for corner location in Monument Box:

12" dia. Hard Maple	N36°E	74.26 feet	Scr. NBT
15" dia. Hard Maple	S43°E	51.95 feet	Scr. NBT
10" dia. Cedar (Existing)	S53°W	50.12 feet	Has X cut on Blazes
5/8" x 24" Iron Rod/2" dia. Alum. cap marked "WITNESS MARKER"	N41°E	48.66 feet	1' E of PP
Metal Survey Sign Post	N32°E	41.2 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca
Surveyor's Michigan License No. 26461

Date Aug. 8, 2000

128