

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Chairman  
RECEIVED FOR RECORD  
DEC 20, AM 9:34  
PAGE # 384, BK 4  
MICHIGAN REGISTER OF DEEDS

For corners in

<u>MENOMINEE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T36N R26W</u>	<u>K-1</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

SAME AS CORNER K-13 T37N-R26W

I, William Lenca, in a field survey on Oct. 02, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by H. Brevort - B.T.'s - Cedar, 14" - N62°W - 22 lks; Cedar, 14" - N33°E - 23 lks. Found remains of both stumps in poor condition in 1992.
- 1992: L.C.R.C. No. 949, Book 3, recorded by William Lenca, RLS No. 26461, states: "Located remnants of original BT stumps by retracement of North Line of Section 2 & portions of North Line of Section 1" - Set 1" x 30" Alum. Pipe/2-1/2" Alum. cap marked MENOMINEE COUNTY SURVEY MARKER: B.T.'s - 8" Ced. - N33°E - 13.72'; 6" Balsam - S76°E - 12.18'; 8" Ced. - S10°W - 8.98'; 8" Ced. - N48°W - 12.83'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a 1 inch diameter aluminum pipe with 2-1/2" diameter aluminum cap and 4 B.T.'s as noted in L.C.R.C. No. 949, Book 3 (described in part "A"). The position of the existing monument fits the stump remnants described in the original survey and noted in part A above. We accepted the existing monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Accepted existing 1" x 30" Aluminum Pipe/2-1/2" Alum. cap - stamped for corner location:

8" dia. Cedar	N33°E	13.72 feet	"X" cut on upper & lower blaze
6" dia. Balsam	S76°E	12.18 feet	"X" cut on upper & lower blaze
8" dia. Cedar	S10°W	8.98 feet	"X" cut on upper & lower blaze
8" dia. Cedar	N48°W	12.83 feet	"X" cut on upper & lower blaze
Metal Survey Sign Post	North	1.4 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Oct. 07, 1996  
Surveyor's Michigan License No. 26461