

PA. Of 1990 On 12/16 1996  
Wm. Davis RLS  
Chairman

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>MENOMINEE</u> (County)	Located in:	Corner Code #
1. Public Land Survey	<u>T36N R26W</u>	<u>K-2</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

REGISTERED FOR RECORD  
96 DEC 20 AM 9 31  
PAGE# 385, BK 4  
BARBARA MORRISON  
REGISTER OF DEEDS  
MICHIGAN STATE BOARD OF SURVEYORS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William Lenca, in a field survey on Sept 18, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2	●	1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1848: Original Survey by Francis Coleman - B.T.'s - Cedar, 12" - S50°W - 20 lks; Cedar, 12" - N46°E - 41 lks. All original evidence for this corner has been destroyed by fire and logging activities.
- 1992: L.C.R.C. No. 949, Book 3, recorded by William Lenca, RLS No. 26461, states: "Set corner on line and proportionately between the NE & SE Corner of Section 2" - Set 1" x 30" Alum. Pipe/2-1/2" Alum. cap marked MENOMINEE COUNTY SURVEY MARKER: B.T.'s - 12" Tam. - N49°E - 52.35'; 6" Balsam - S24°E - 32.97'; 10" Balsam - S28°W - 14.38'; 8" Balsam - N73°W - 20.70'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We found a 1 inch diameter aluminum pipe with 2-1/2" diameter aluminum cap and 4 B.T.'s as noted in L.C.R.C. No. 949, Book 3 (described in part "A"). The position of the existing monument fits the single proportionate position between the NE Corner and the SE Corner of Section 2, T36N-R26W, and is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Accepted existing 1" x 30" Aluminum Pipe/2-1/2" Alum. cap - stamped for corner location:

12" dia. Tamarack	N49°E	52.35 feet	"X" cut on upper & lower blaze
6" dia. Balsam	S24°E	32.97 feet	"X" cut on upper & lower blaze
10" dia. Balsam	S28°W	14.38 feet	"X" cut on upper & lower blaze
8" dia. Balsam	N73°W	20.70 feet	"X" cut on upper & lower blaze

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date Oct. 07, 1996