

P.A. Of 1990 On 12/12 1996

Mr. David P. G.S.  
Chairman

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

|                                       |                           |               |
|---------------------------------------|---------------------------|---------------|
| <u>MENOMINEE</u><br>(County)          | Located In:               | Corner Code # |
| 1. Public Land Survey                 | T <u>36N</u> R <u>26W</u> | <u>L-1</u>    |
|                                       | T _____ R _____           | _____         |
|                                       | T _____ R _____           | _____         |
|                                       | T _____ R _____           | _____         |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____   | _____         |
|                                       | S _____ T _____ R _____   | _____         |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____   | _____         |
|                                       | S _____ T _____ R _____   | _____         |

RECEIVED FOR RECORD  
56 DEC 20 AM 9 34  
PAGE # 386, 1344  
DANIELA MORRISON  
REGISTER OF DEEDS  
REGISTERED OFFICE  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

SAME AS CORNER L-13 T37N-R26W

I, William Lenca, in a field survey on Sept. 18, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

|    |   |    |   |    |   |    |   |    |   |    |   |    |   |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
|    | A | B  | C | D  | E | F  | G | H  | I | J  | K | L  | M |
| 1  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 2  |   | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |
| 3  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 4  |   | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |
| 5  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 6  |   | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |
| 7  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 8  |   | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |
| 9  |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 10 |   | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |
| 11 |   |    |   |    |   |    |   |    |   |    |   |    |   |
| 12 |   | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |
| 13 |   |    |   |    |   |    |   |    |   |    |   |    |   |

A. Description of original monument and accessories and/or subsequent restoration:

1848: Original Survey by H. Brevoort - B.T.'s - Cedar, 4" - N46°E - 18 lks; Cedar, 12" - N17°W - 20 lks. All original evidence for this corner has been destroyed by fire and logging activities.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We located the single proportional position for this corner between the NW Corner and the NE Corner of Section 1, T36N-R26W, and searched this area for original evidence. Finding no such evidence, we set the corner at the above mentioned proportional location and found that it fit well with a GLO terrain call to a swamp edge 198 feet to the west. We accepted this location as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Set 2" dia. Aluminum Pipe/3-1/4" dia. Alum cap stamped for corner location:

|                        |       |            |          |
|------------------------|-------|------------|----------|
| 10" dia. Cedar         | N20°E | 27.32 feet | Scr. NBT |
| 18" dia. Cedar         | S82°E | 32.81 feet | Scr. NBT |
| 16" dia. Cedar         | S00°W | 24.03 feet | Scr. NBT |
| 5" dia. Cedar          | N67°W | 15.28 feet | Scr. NBT |
| Metal Survey Sign Post | South | 0.8 feet   |          |

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca  
Surveyor's Michigan License No. 26461

Date Oct. 07, 1996