

Approved by Menominee County
 Land Survey Remonumentation
 Peer Group Under Act 345 Of
 P.A. Of 1990 On 12/12 1996
McDavin RW
 Chairman

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MENOMINEE
 (County)
 Located In: Corner Code #

1. Public Land Survey		T <u>36</u> N R <u>26</u> W	<u>M-3</u>
		T___ R___	_____
		T___ R___	_____
		T___ R___	_____
2. Property Controlling in Section	S___	T___ R___	_____
	S___	T___ R___	_____
3. Miscellaneous Property in Sec.	S___	T___ R___	_____
	S___	T___ R___	_____

REGISTER OF DEEDS
 96 DEC 20 AM 9 34
 FILE # 388 BK 4
 REGISTER OF DEEDS STAMP & FILE NUMBER

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____
 SAME AS CORNER A-3 T36N-R25W

I, William Lenca, in a field survey on Sept. 11, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1848: Original Survey by John Mullett - B.T.'s - Sugar, 12" - S50°W - 11 lks; Fir, 10" - N22°W - 20 lks. All original evidence for this corner has been destroyed by fire and logging activities.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

We located the single proportional position for this corner between the NE Corner of Section 1 and the SE Corner of Section 12, T36N-R26W, and searched this area for original evidence. Finding no such evidence, we set the corner at the above mentioned proportional location and found that it fit well with the GLO Notes stating that the corner fell on the South Margin of a Swamp. We accepted this location as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2" dia. Aluminum Pipe/3-1/4" dia. Alum cap stamped for corner location:

12" dia. White Spruce	N32°E	20.38 feet	Scr. NBT
6" dia. White Ash	S41°E	26.48 feet	Scr. NBT
9" dia. Cedar	S48°W	43.46 feet	Scr. NBT
5" dia. Cedar	N70°W	16.39 feet	Scr. NBT
Metal Survey Sign Post	North	1.1 feet	

NOTE: All bearings are magnetic bearings. All distances are measured with steel tape. Distances to trees are to nail in side of tree.

Signed by William Lenca Date Oct. 07, 1996
 Surveyor's Michigan License No. 26461

388