

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>36</u> N. S., R. <u>27</u> E. W.	<u>E-7</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on September 22 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

E-7 S.W. section corner - Section 16; Wood Post; Hem. 18 - N45°W - 4 lks.; Hem. 24 - 856°E - 3 1/4 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

E-7 Searched for O.B.T.'s but nothing found. There is a county road built along the east 1/4 of the south line of Sec. 17 but it has a definite deflection at the approximate E. 1/16 corner and the centerline of road is obviously about 80' too far north at the section corner (S.W. corner of Sec. 16). This corner was therefore set in line with the westerly portion of said county road and in line with an old fence north and is very near the double proportionate position for the corner. It also fits a stream call north 27.58 chs. and a swamp call south 25.91 chs.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-7 1" pipe, 4" aluminum cap; 10" W. Birch - N52°W - 39.0'; 4" Spruce - S62°W - 20.5'; S.W. corner of concrete block foundation for cabin - 857°E - 92.8'; N.W. corner of concrete block foundation for cabin - 872°E - 82.5'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 1-26-81
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558