

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>36</u> N. S., R. <u>27</u> E. W.	<u>G-9</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, **David B. Babbitt** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on September 2, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

G-9 S.W. Section corner - Section 22; Wood Post, Cedar 10 - N12°W - 9 lks.; Cedar 12-S52°E - 36 lks.; no sign of these at this time. No N.B.T.'s of record from Wm. Parrots work.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

G-9 Set in centerline of old E-W road grade and at a point in line with an old blased cedar stub (N26°W - 26') believed to have been marked by Wm. Parrot who is said to have done survey work in Sec. 22 in the late 1930's. This position for this corner places the S. ¼ corner of Sec. 22 at record measurement west of a small stream (400.0' east) and the E. 1/16 corner on the south line of Sec. 21 falls just east of an old farm fence at the east edge of a field.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-9 1" pipe, 4" aluminum cap buried in road; 8" Y. Birch - N10°W - 18.8'; 4" Cedar - N34°E - 19.3'; 7" Cedar - S66°W - 18.5'; 6" Cedar - S1°E - 10.5'; Old Blased Cedar Stub - N26°W - 26.0'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 1-26-81
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558