

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF -: | LOCATED IN -: | CORNER CODE NUMBER |
|--|--|--------------------|
| 1. PUBLIC LAND SURVEY _____ | T. <u>36</u> N. S., R. <u>27</u> E. W. | <u>E-10, F-9</u> |
| 2. PROPERTY CONTROLLING IN SECTION <u>28</u> | T. <u>36</u> N. S., R. <u>27</u> E. W. | <u>2</u> |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | T. _____ N. S., R. _____ E. W. | _____ |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on September 3 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- E-10** West 1/4 corner, Section 28; Wood Post, Cedar 12 - N46°E - 84 lks.; Cedar 12 - S58°W - 73 lks.
- F-9** North 1/4 corner, Section 28; Wood Post, Cedar 12 - N47°E - 58 lks.; Cedar 14 - S51°W - 63 lks.
- 2** East 1/16 on the north section line, Section 28; not previously established.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-10** Set in line with old fences west and north and centerline of roads east and south.
- F-9** Set in the centerline of a N-S county road and in line with old fences east and west. Measurements east and west are reasonable.
- 2** Set M.P.O.L. between the North 1/4 corner and the N.E. section corner of Section 28.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- ALL** - 1" pipe, 4" aluminum cap.
- E-10** 10" W. Pine - S34°E - 53.0'; 8" H. Maple - N35°W - 18.4'; 9" W. Pine - S40°W - 49.0'; 10" W. Pine - N55°E - 100.1'
- F-9** 5" W. Pine - S14°W - 80.6'; 4" Aspen - N84°W - 38.2'; 8" R. Pine - N63°E - 92.6'; Gate Post 6" - S36°E - 23.3'.
- 2** 8" B. Cherry - S65°E - 2.65'; 5" Ironwood - S33°W - 16.1'; 4" Twin H. Maple - N6°W - 91.7'; 9" H. Maple - N35°E - 36.5'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 1-26-81
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558