

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____	N. _____ E. _____ S., R. _____ W. _____	_____
2. PROPERTY CONTROLLING IN SECTION <u>16</u> , T. <u>36</u>	N. _____ E. _____ S., R. <u>27</u> W. _____	<u>3, 8, 10, 15</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____	N. _____ E. _____ S., R. _____ W. _____	_____
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on September 30 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- 3 North 1/16 corner on the west section line - Sec. 16; not previously established.
 - 8 West 1/16 corner - Sec. 16; 4" Cedar Post - set 1902. No N.B.T.'s.
 - 10 South 1/16 - west boundary - Sec. 16; not previously established.
 - 15 West 1/16 corner on the south section line - Sec. 16; not previously established.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- 3 Set M.P.O.L. between the West 1/4 corner and the N.W. section corner of Section 16.
 - 8 Set M.P.O.L. between the center of section and the west 1/4 corner of Sec. 16. Searched for old post but found nothing.
 - 10 Set M.P.O.L. between the west 1/4 corner and the S.W. section corner of Section 16.
 - 15 Set M.P.O.L. between the South 1/4 corner and the S.W. section corner of Section 16.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- ALL 1" pipe, 4" aluminum cap.
- 3 9" (Twin) Cedar - N13°E - 25.8'; 4" Balsam - N88°E - 2.0'; 9" R. Maple - S50°W - 13.5'; 4" B. Ash - West - 18.95'.
 - 8 8" Aspen - S34°W - 28.6'; 10" H. Maple - S31°W - 59.0'; 9" R. Maple - N85°W - 40.3'; 3" Aspen - N21°E - 18.7'.
 - 10 12" Balsam Fir - N19°W - 25.0'; 9" H. Maple - S75°W - 23.5'; 5" Lynn - N67°E - 17.5'; 6" H. Maple - S41°E - 40.7'; 5.6' East to centerline N. and S. truck trail.
 - 15 4" Maple - N8°W - 50.0'; 12" Spruce - N51°E - 61.4'; 10" Twin Top Maple - S15°E - 64.1'; Power pole - S33°W - 37.5'.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY DATE 1-26-81
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558