

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF—:	LOCATED IN—:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>36</u> N. S., R. <u>27</u> E. W.	<u>G-6</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

**MENOMINEE  
CO.**

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, David B. Subbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on August 18 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

E  $\frac{1}{4}$  corner  
Wood post  
Tam. 12 - N15°W - 35 lks.  
Tam. 8 - S27°E - 46 lks.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

Found both Tam. O.B.T.s N.W. one - trunk of tree lying in muck, both faces with plain scribing.  
S.E. one is a stump with part of lower face and plainly scribed "B.T."  
Bearings and distances fit well.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

1" pipe, 4" aluminum cap and cedar post  
7" cedar - S52°E - 21.0'; 8" cedar - N88°E - 6.9'; 9" cedar - N35°E - 6.0';  
11" cedar - N64°W - 25.8'

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558